

Fiscal Prudence and Risk Management in Megaprojects: A Longitudinal Analysis of Stuttgart 21

Dr. Markus Weber

Institute of Construction Management and Economics, Technical University of Munich, Germany

Prof. Anna Schmidt

Department of Civil Engineering, University of Stuttgart, Germany

Article received: 05/04/2025, Article Revised: 06/05/2025, Article Accepted: 01/06/2025

DOI: <https://doi.org/10.55640/ijmbd-v02i06-01>

© 2025 Authors retain the copyright of their manuscripts, and all Open Access articles are disseminated under the terms of the [Creative Commons Attribution License 4.0 \(CC-BY\)](#), which licenses unrestricted use, distribution, and reproduction in any medium, provided that the original work is appropriately cited.

ABSTRACT

Megaprojects, characterized by their immense scale, complexity, and significant public and private investment, frequently face substantial financial and risk management challenges. Cost overruns, schedule delays, and unforeseen complexities are common, often leading to public scrutiny and economic strain. This article presents a longitudinal study of Stuttgart 21, a prominent railway and urban development project in Germany, to examine the intricacies of financial management and risk mitigation strategies in such ventures. By tracing the project's evolution from its inception to its current status, this analysis highlights key financial decisions, funding mechanisms, and the various risks encountered, including technical, political, environmental, and financial. The study identifies critical factors contributing to cost escalation and delays, assesses the effectiveness of implemented risk mitigation measures, and draws broader implications for the successful delivery of future megaprojects. The case of Stuttgart 21 offers valuable insights into the dynamic interplay between project governance, stakeholder management, and the inherent uncertainties of large-scale infrastructure development.

Keywords: Megaprojects, Financial Management, Risk Mitigation, Stuttgart 21, Cost Overruns, Project Management, Infrastructure Development, Germany.

INTRODUCTION

Megaprojects are transformative undertakings, often involving investments exceeding one billion US dollars, impacting millions of people, and spanning decades in their lifecycle [10, 25]. These ventures, ranging from high-speed rail networks to urban regeneration schemes, are critical drivers of economic growth and societal development. However, their inherent complexity, long lead times, and exposure to a multitude of internal and external factors make them particularly susceptible to significant financial and operational risks [1]. A recurring theme in the literature on megaprojects is the prevalence of cost overruns and schedule delays, often leading to substantial deviations from initial estimates and considerable public debate [10, 22]. The effective management of finances and the proactive mitigation of risks are thus paramount for the successful delivery of

these ambitious endeavors [1, 22, 34].

Financial management in megaprojects encompasses the planning, organizing, directing, and controlling of financial resources to achieve project objectives [2]. It involves securing adequate funding, managing cash flows, controlling costs, and ensuring financial transparency and accountability throughout the project lifecycle. Risk mitigation, on the other hand, involves identifying, assessing, and developing strategies to reduce the impact of potential adverse events [14]. For megaprojects, risks can stem from various sources, including technical complexities, regulatory changes, political opposition, environmental concerns, and fluctuating economic conditions [12, 21]. The interplay between financial decisions and risk exposure is particularly critical, as inadequate risk management can

directly translate into financial distress and project failure [10].

This article undertakes a longitudinal study of Stuttgart 21, a monumental railway and urban development project in Stuttgart, Germany, to provide an in-depth analysis of financial management and risk mitigation within a real-world megaproject context. Stuttgart 21, conceived in the early 1990s, involves the transformation of the city's main railway station into an underground through-station, alongside extensive urban development and new railway lines [4, 30]. This project has been a subject of intense public and political debate, primarily due to its escalating costs and prolonged construction period [3, 18, 28]. By examining the financial evolution and risk management strategies employed throughout the project's history, this study aims to contribute to a deeper understanding of the challenges inherent in megaproject delivery and to identify lessons learned that can inform future large-scale infrastructure initiatives. The longitudinal approach allows for an analysis of how financial and risk landscapes evolve over time, and how initial assumptions and mitigation plans adapt, or fail to adapt, to unfolding realities.

METHODS

This study employs a qualitative, longitudinal case study methodology to investigate financial management and risk mitigation in the Stuttgart 21 megaproject. A longitudinal approach is crucial for understanding the dynamic nature of financial and risk factors over the project's extended lifecycle, from its conceptualization in the early 1990s through its ongoing construction. The data collection and analysis involved several key stages:

1. **Documentary Analysis:** Extensive review of publicly available project documents, official reports, feasibility studies, and financial agreements was conducted. This included:

- o Initial feasibility studies and cost estimates from the 1990s [7].
- o The 2009 financing agreement between Deutsche Bahn, the state of Baden-Württemberg, the city of Stuttgart, the Stuttgart Region Association, and Stuttgart Airport GmbH [9].
- o Annual reports and integrated reports from Deutsche Bahn AG, providing insights into the project's financial performance and overall corporate financial health [5, 19].
- o Official project websites and chronologies maintained by DB Projekt Stuttgart–Ulm GmbH, detailing project milestones, cost updates, and historical developments [4, 29, 30].

- o Parliamentary resolutions and government statements related to the project's funding and progress [20].

2. **Media and Public Discourse Analysis:** A comprehensive review of German news articles, particularly from major publications like DER SPIEGEL [3, 18], tagesschau.de [15], ZDFheute [16], Wirtschaftswoche.de [23], and SWR Aktuell [28], was undertaken. This provided insights into public perception, political debates surrounding cost increases, and the evolution of risk perceptions over time. Environmental organizations' perspectives were also considered [26].

3. **Literature Review on Megaproject Management:** A thorough review of academic literature on megaproject management, financial intelligence, and risk management was conducted to establish a theoretical framework for analysis. This included concepts such as:

- o Megaproject success factors and common challenges [1, 8, 10, 13, 17, 22, 24, 25, 33, 34].
- o Risk breakdown structures and their application in project management [14].
- o The importance of financial intelligence in project oversight [2].
- o The role of relational quality and incentives in project success [33].

4. **Longitudinal Data Mapping:** Key financial figures (initial estimates, revised budgets, actual expenditures), project milestones, and reported risks were systematically mapped across the project's timeline. This allowed for the identification of points of significant cost escalation, delays, and the emergence of new risks.

5. **Qualitative Content Analysis:** The collected data was subjected to qualitative content analysis to identify recurring themes related to financial decision-making, sources of cost overruns, types of risks encountered, and the effectiveness of mitigation strategies. Specific attention was paid to how financial responsibilities were allocated and contested among stakeholders [9, 11, 15, 16, 23].

By integrating information from official project documentation, financial reports, media coverage, and academic literature, this methodological approach provides a robust framework for a comprehensive longitudinal analysis of financial management and risk mitigation in the Stuttgart 21 megaproject.

RESULTS

The longitudinal analysis of Stuttgart 21 reveals a complex narrative of evolving financial estimates,

persistent cost overruns, and a continuous struggle with various risks, underscoring the inherent challenges in managing megaprojects.

Financial Evolution and Cost Escalation

The financial trajectory of Stuttgart 21 has been marked by significant and recurring cost increases, a common characteristic of megaprojects globally [10].

- **Initial Estimates (1990s):** Early feasibility studies in the mid-1990s estimated the project cost at approximately €2.5 billion [7]. This initial figure served as the baseline for early planning and public discussions.
- **2009 Financing Agreement:** A pivotal moment was the 2009 financing agreement, which set the project budget at €4.5 billion [9]. This agreement distributed financial responsibility among Deutsche Bahn AG, the state of Baden-Württemberg, the city of Stuttgart, the Stuttgart Region Association, and Stuttgart Airport GmbH. This marked a substantial increase from the initial estimates, already highlighting early challenges in cost control.
- **Subsequent Revisions and Escalation:** Following the 2009 agreement, costs continued to escalate dramatically. By 2011, reports indicated that the project was already facing significant financial challenges, with discussions of increased costs [3]. Subsequent revisions pushed the estimated costs to €6.5 billion by 2013, then to €8.2 billion by 2018, and further to over €9 billion by 2020. The most recent estimates place the total cost at over €11 billion, with discussions about potential further increases [15, 28]. This represents a more than fourfold increase from the initial estimates.
- **Funding Mechanisms and Disputes:** The project has been primarily funded through a combination of federal government contributions, state and municipal funds, and Deutsche Bahn's own investments [9]. The escalating costs have led to protracted legal disputes among the financing partners, particularly regarding who is responsible for covering the additional expenses beyond the agreed-upon budget [11, 15, 16, 23]. Recent court decisions in 2024 have largely ruled that Deutsche Bahn is responsible for the majority of these additional costs [11, 16]. This highlights the critical importance of clear financial agreements and risk-sharing mechanisms from the project's inception. Deutsche Bahn's overall financial health, as reflected in its integrated reports and net income figures, has also been impacted by such large-scale projects [5, 19].

Risk Identification and Mitigation Challenges

Stuttgart 21 has encountered a wide array of risks, many of which were either underestimated or inadequately mitigated, contributing significantly to cost overruns and

delays.

- **Technical and Geological Risks:** The project's ambitious engineering, involving the construction of a subterranean station and tunnels through complex geological formations, presented significant technical risks. Unexpected geological conditions, particularly the presence of anhydrite, led to major construction challenges and delays, requiring costly remediation efforts [12]. These technical complexities often translate directly into financial impacts [21].
- **Environmental and Regulatory Risks:** Environmental concerns, particularly regarding the protection of endangered species (e.g., bats in the park area), led to legal challenges and delays [26]. Adherence to stringent environmental regulations and the need for extensive mitigation measures added both time and cost to the project.
- **Political and Social Risks:** From its early stages, Stuttgart 21 faced substantial public opposition and political resistance [18]. Large-scale protests, legal challenges, and shifts in political leadership (e.g., the change in state government in Baden-Württemberg in 2011 [3, 20]) created significant uncertainty and impacted project progress. The ongoing public debate and political scrutiny forced repeated re-evaluations and justifications of the project, diverting resources and attention. The ability to manage stakeholders and public perception is a critical success factor for megaprojects [17, 33].
- **Financial Risks:** Beyond the direct cost of technical and environmental issues, the project faced inherent financial risks related to long-term planning. Inflation, unforeseen material cost increases, and changes in labor costs over a multi-decade project lifecycle were difficult to predict and account for in initial budgets [10, 12]. The lack of a robust risk breakdown structure early on may have contributed to these financial vulnerabilities [14].
- **Project Management and Governance Risks:** While Deutsche Bahn established a dedicated project company (DB Projekt Stuttgart–Ulm GmbH) [29], the sheer scale and complexity of Stuttgart 21 tested its project management systems [1]. Challenges in defining project lead time effectively [8], measuring project readiness [24], and identifying critical success factors [13, 22, 34] became apparent. The relationship between relational quality among stakeholders and project success also played a role [33]. The project's history demonstrates that despite efforts to manage it as a conventional project, megaprojects often require a different approach to governance and oversight [1, 25].

In summary, the results indicate that while initial financial planning was undertaken, the project's financial

management was consistently reactive to unforeseen risks and escalating costs. Risk mitigation efforts, though present, were often overwhelmed by the magnitude and interconnectedness of technical, environmental, political, and financial challenges. The longitudinal perspective highlights how early underestimations and inadequate risk foresight compounded over time, leading to the current situation of significant cost overruns and prolonged delays.

DISCUSSION

The longitudinal study of Stuttgart 21 offers a compelling illustration of the profound challenges inherent in the financial management and risk mitigation of megaprojects. The project's journey from an initial €2.5 billion estimate to current figures exceeding €11 billion, coupled with significant delays, underscores a recurring pattern in large-scale infrastructure development globally [10]. This case reinforces several critical lessons for future megaprojects.

Firstly, the experience of Stuttgart 21 highlights the pervasive issue of optimism bias and strategic misrepresentation in initial project estimations. As Flyvbjerg (2017) argues, megaprojects are "over budget, over time, over and over" [10]. The substantial discrepancy between the early feasibility study [7] and the actual costs demonstrates a fundamental failure in accurately forecasting the project's financial demands and associated risks. This is not unique to Stuttgart 21 but is a systemic problem in megaproject planning, where political and economic incentives can lead to underestimation of costs and overestimation of benefits to secure approval [10]. A more rigorous and independent assessment of financial intelligence and risk profiles from the outset, as advocated by Berman and Knight [2], is essential to counter this bias.

Secondly, the case vividly demonstrates the interconnectedness and cascading nature of risks in megaprojects. Technical challenges, such as unexpected geological conditions [12], were not isolated incidents but triggered a chain reaction of delays, increased material and labor costs, and subsequent financial disputes among stakeholders [11, 15, 16, 23]. Similarly, environmental concerns and public opposition [18, 26] translated into legal battles and political pressures, further impacting the project's timeline and budget. This underscores the need for a holistic and adaptive risk management framework that goes beyond simple risk identification to model complex interdependencies and potential ripple effects [14]. The "fog of war" concept, often applied to military strategy, finds a parallel in the inherent uncertainties of megaproject execution [4].

Thirdly, governance and stakeholder management emerged as critical determinants of financial and risk outcomes. The protracted legal disputes over cost

responsibility [11, 15, 16, 23] highlight deficiencies in the initial financing agreement [9] and the broader governance structure. A lack of clear, unambiguous risk-sharing mechanisms and dispute resolution processes exacerbated financial burdens and prolonged uncertainties. Effective stakeholder engagement, including addressing public concerns and managing political shifts, is paramount for maintaining project legitimacy and mitigating non-technical risks [17, 18, 33]. The evolution of the project's political landscape, from initial broad support to significant public protest [18] and changes in regional government [3, 20], profoundly impacted its trajectory.

Finally, the Stuttgart 21 case underscores the importance of longitudinal learning and adaptive project management. Megaprojects, by their very nature, are long-term endeavors [8]. Initial plans and risk assessments, no matter how thorough, will inevitably encounter unforeseen circumstances. The ability to continuously monitor, reassess, and adapt financial and risk mitigation strategies throughout the project lifecycle is crucial. This involves not only technical adjustments but also a willingness to revisit fundamental assumptions and engage in transparent communication with all stakeholders regarding evolving costs and timelines [28]. The project's "readiness" at various stages, and the factors contributing to its success or failure, are complex and multi-faceted [22, 24, 34].

In conclusion, Stuttgart 21 serves as a powerful cautionary tale and a rich learning opportunity. While the project is nearing completion, its journey has been a testament to the immense financial and risk management challenges inherent in megaprojects. The lessons learned from its cost overruns, delays, and disputes emphasize the need for greater realism in initial planning, more robust and interconnected risk management frameworks, stronger governance structures with clear financial accountability, and a commitment to continuous adaptation and stakeholder engagement throughout the entire project lifecycle.

CONCLUSION

The comprehensive longitudinal analysis of Stuttgart 21 unequivocally demonstrates that effective financial management and robust risk mitigation are not merely desirable, but absolutely critical for the successful delivery of megaprojects. The project's trajectory, marked by a dramatic escalation in costs from initial estimates and significant delays, serves as a compelling case study of the multifaceted challenges inherent in large-scale infrastructure development.

The study has highlighted that the initial financial planning for Stuttgart 21 suffered from significant underestimation, a common pitfall in megaprojects often attributed to optimism bias and strategic

misrepresentation [10]. This foundational flaw set the stage for subsequent financial pressures and disputes among the funding partners. Furthermore, the project's prolonged timeline exposed it to a dynamic array of risks – technical, geological, environmental, political, and social – many of which were either unforeseen or inadequately addressed in early planning stages. The cascading effects of these risks, particularly the unexpected geological complexities and persistent public and political opposition, directly translated into substantial cost overruns and schedule slippages.

The experience of Stuttgart 21 underscores the imperative for a paradigm shift in megaproject governance and execution. Future projects must prioritize:

1. **Realistic and Transparent Financial Forecasting:** Moving beyond optimistic biases to develop more accurate and comprehensive cost estimates that account for inherent uncertainties and potential risks from the outset.
2. **Integrated and Adaptive Risk Management:** Implementing holistic risk frameworks that identify, assess, and manage interconnected risks across all project dimensions, with a strong emphasis on continuous monitoring and adaptive strategies. The use of tools like a Risk Breakdown Structure [14] can be foundational.
3. **Robust Governance and Clear Accountability:** Establishing clear financial agreements, risk-sharing mechanisms, and dispute resolution processes among all stakeholders to prevent protracted legal battles and ensure accountability for cost escalations.
4. **Proactive Stakeholder Engagement:** Recognizing that political and social risks are as critical as technical ones, and engaging proactively with the public, environmental groups, and political actors throughout the project lifecycle to build consensus and mitigate opposition.

While Stuttgart 21 is an example of a megaproject that has faced considerable adversity, its ongoing completion offers invaluable lessons. By learning from such experiences, future large-scale infrastructure projects can adopt more prudent financial practices, implement more comprehensive risk mitigation strategies, and ultimately enhance their chances of successful delivery, contributing to economic growth and societal benefit without the excessive burdens of cost overruns and delays. The insights from Stuttgart 21 reinforce the global call for improved megaproject management systems and a deeper understanding of the critical drivers of success and failure [1, 22, 34].

REFERENCES

- Ashkanani, S., & Franzoi, R. (2022). An overview on megaproject management systems. *Management Matters*, 19(2), 129-148. <https://doi.org/10.1108/MANM-01-2022-0006>
- Berman, K., & Knight, J. (2013). *Financial Intelligence*. Harvard Business Review Press.
- Böll, S. (2011). Grün-rot und stuttgart 21: Viel Geld, Wenig Bahnhof. *DER SPIEGEL*. Retrieved from <https://www.spiegel.de/wirtschaft/unternehmen/grue-n-rot-und-stuttgart-21-viel-geld-wenig-bahnhof-a-759527.html>
- DB Projekt Stuttgart–Ulm. (n.d.). Stuttgart 21-Überblick. *Bahnprojekt Stuttgart- Ulm*. Retrieved from <https://www.bahnprojekt-stuttgart-ulm.de/projekt/ueberblick/stuttgart-21/>
- Deutsche Bahn 2022 Integrated Report. (2022). Deutsche Bahn AG.
- Deutsche Bahn. (n.d.). Architektur. *Bahnprojekt*. Retrieved from <https://www.bahnprojekt-stuttgartulm.de/projekt/stuttgart-filder-s21/neue-bahnhoefe/hauptbahnhof-stuttgart/architektur/>
- Die Machbarkeitsstudie | Projekt “Stuttgart 21.” (1996). Deutsche Bahn AG.
- Eduardo Yamasaki Sato, C., & De Freitas Chagas Jr, M. (2014). When do megaprojects start and finish? Redefining project lead time for megaproject success. *International Journal of Managing Projects in Business*, 7(4), 624-637. <https://doi.org/10.1108/IJMPB-07-2012-0040>
- Finanzierungsvertrag (2009). DB Netz AG, Land Baden-Württemberg, Landeshauptstadt Stuttgart, Verband Region Stuttgart, Flughafen Stuttgart GmbH.
- Flyvbjerg, B. (2017). Megaprojects: Over Budget, Over Time, Over and Over. Cato Institute. Retrieved from <https://www.cato.org/policy-report/january/february-2017/megaprojects-over-budget-over-time-over-over>
- Gerichtsentscheidung über S-21-Mehrkostenklage der Bahn. (2024). *Baden-Württemberg.de*. Retrieved from <https://www.badenwuerttemberg.de/de/service/press-e/pressemitteilung/pid/verwaltungsgerichtsentscheidung-zur-stuttgart-21-klage>
- Großprojekt Stuttgart 21- Wendlingen- Ulm Chancen und Risiken (2011). DB Projekt Bau GmbH.
- He, Q., Xu, J., Wang, T., & Chan, A. P. C. (2021). Identifying the driving factors of successful

megaproject construction management: Findings from three Chinese cases. *Frontiers of Engineering Management*, 8(1), 5-16. <https://doi.org/10.1007/s42524-019-0058-8>

Hillson, D. (2003). Using a Risk Breakdown Structure in project management. *Journal of Facilities Management*, 2(1), 85-97. <https://doi.org/10.1108/14725960410808131>

Hörger, D. (2023). Verwaltungsgericht verhandelt über Klage der Bahn zu "Stuttgart 21"-kosten. *tagesschau.de*. Retrieved from <https://www.tagesschau.de/wirtschaft/finanzen/kosten-stuttgart-21-verhandlung-100.html>

Houben, L. (2024). Stuttgart 21: Bahn muss Mehrkosten zahlen. *ZDFheute*. Retrieved from <https://www.zdf.de/nachrichten/politik/deutschland/stuttgart-21-mehrkosten-urteil-deutsche-bahn-100.html>

Hu, Y., Chan, A. P. C., & Le, Y. (2015). Understanding the Determinants of Program Organization for Construction Megaproject Success: Case Study of the Shanghai Expo Construction. *Journal of Management in Engineering*, 31(5), 05014019. [https://doi.org/10.1061/\(ASCE\)ME.1943-5479.0000310](https://doi.org/10.1061/(ASCE)ME.1943-5479.0000310)

Kaiser, S., & Windmann, A. (2010). The "Stuttgart 21" Revolt: Protests Against Mega Project Grow. *Der Spiegel*. Retrieved from <https://www.spiegel.de/international/germany/the-stuttgart-21-revolt-protests-against-megaproject-grow-a-713375.html>

Koptyug, E. (2023). Deutsche Bahn net income 2022. *Statista*. Retrieved from <https://www.statista.com/statistics/936104/deutsche-bahn-net-incomegermany/#:~:text=This%20statistic%20shows%20the%20net,amounted%20to%20%2D227%20million%20euros.>

Landtag von Baden-Württemberg Entschließung von Stuttgart 21 (2006). Land Baden-Württemberg.

Locatelli, G., Littau, P., Brookes, N. J., & Mancini, M. (2014). Project Characteristics. Enabling the Success of Megaprojects: An Empirical Investigation in the Energy Sector. *Procedia - Social and Behavioral Sciences*, 119, 625-634. <https://doi.org/10.1016/j.sbspro.2014.03.070>

Mišić, S., & Radujković, M. (2015). Critical Drivers of Megaprojects Success and Failure. *Procedia*

Engineering, 122, 71-80. <https://doi.org/10.1016/j.proeng.2015.10.009>

Prozess: Wer zahlt die Milliarden-Mehrkosten von Stuttgart 21? (2023, May 8). *Wirtschaftwoche.de*. Retrieved from <https://www.wiwo.de/politik/deutschland/prozess-der-zahlt-die-milliarden-mehrkosten-von-stuttgart-21/29138966.html>

Shenoy, D., & Mahanty, B. (2021). Measuring the readiness of a megaproject. *International Journal of Managing Projects in Business*, 14(4), 999-1022. <https://doi.org/10.1108/IJMPB-05-2020-0154>

Söderlund, J., Sankaran, S., & Biesenthal, C. (2017). The past and Present of Megaprojects. *Project Management Journal*, 48(6), 5-16. <https://doi.org/10.1177/875697281704800602>

Stuttgart 21 und Artenschutz. (n.d.). *BUND - BUND für Naturschutz und Umwelt in Deutschland*. Retrieved July 1, 2024, from <https://www.bund-bawue.de/themen/mensch-umwelt/stuttgart-21/stuttgart-21-undartenschutz/>

Stuttgart 21: Eine ausführliche Kompaktchronologie. (n.d.). *ansTageslicht.de*. Retrieved from <https://www.anstageslicht.de/macht-und-staatsapparat/stuttgart-21/stuttgart-21-eine-ausfuehrlichekompaktchronologie>

SWR Aktuell (2024, May 7). Stuttgart 21: Chronologie der Kostenexplosion. Retrieved from <https://www.swr.de/swraktuell/baden-wuerttemberg/s21-stuttgart-21-kosten-chronologie-100.html>

Über uns: DB Projekt Stuttgart–Ulm GmbH. (n.d.). *Bahnprojekt-Stuttgart-Ulm.de*. Retrieved from <https://www.bahnprojekt-stuttgart-ulm.de/ueber-us/db-projekt-stuttgartulm/>

Ursprung & Chronologie (n.d.). *Bahnprojekt-Stuttgart-Ulm.De*. Retrieved July 2, 2024, from <https://www.bahnprojekt-stuttgart-ulm.de/projekt/historie/ursprung-chronologie/>

Verzuh, E. (2021). *Project Management: A Platform for Innovation*. In *The Fast Forward MBA in Project Management* (6th ed.).

Verzuh, E. (2021). *The fast forward MBA in project management: The comprehensive, easy-to-read handbook for beginners and pros* (6th ed.). Wiley.

Wang, D., Fu, H., & Fang, S. (2019). The Relationship Between Relational Quality and Megaproject Success: The Moderating Role of Incentives. *Engineering Management Journal*, 31(4),

257-269.

<https://doi.org/10.1080/10429247.2019.1624099>

Wang, T., Xu, J., He, Q., Chan, A. P. C., & Owusu, E. K. (2022). Studies on the success criteria and critical success factors for mega infrastructure construction projects: A literature review. *Engineering, Construction and Architectural Management*, 30(5), 1809-1834.
<https://doi.org/10.1108/ECAM-12-2020-1042>